



Hydra Service, Inc.
SPECIALIST IN FLUID MOVEMENT



250 Springview Commerce Drive
Debarry Florida 32713
Phone: 407 330 3456
Phone: 800 323 1731
Fax: 407 330 3404

**Sales Representative
Contact Information**
Cell Phone: 407-790-9751

TO: **City of Edgewater**
ATTN: **Tanner Redd**

FROM: **Dale Jahn**
EMAIL: dale@hydraservice.net
DATE: **February 27, 2026**
QUOTE: **260227-3DJ**
REF: **Edgewater LS 9 Rehab**

- 2 Sulzer/ABS model XFP80C-VX.3-PE22/4 submersible wastewater pump, 3hp, 3-230/460v, with 49' of motor cable. Includes hardened impeller.
- 2 5 year, 100% warranty for XFP80C-VX.3-PE22/4.
- 2 3" Sulzer / ABS base elbow (dual guide rail design) including slide bracket with hardware and rubber sealing grommet.
- 2 Upper guide rail bracket, 2" dual rail, 316 stainless steel.
- 4 10' length of 2" diameter guide rail, 316 stainless steel.
- 2 10' pump lifting chain with shackle, 316 stainless steel.
- 1 Duplex pump control panel to City of Edgewater standards, 3hp, 1/230v. Includes VFDs for 1-phase to 3-phase conversion.
- 4 Liquid level sensing float with 60' of cable.
- 1 Mission Communications M152 RTU with 3 year service plan.
- 1 USEMCO factory-built duplex "top vault" system including fabricated aluminum base for 4' diameter wetwell with access hatch, 3" sch 40 316SS piping, cast iron plug valves, cast iron check valves, 3" emergency pump out connection with cast iron isolation valve & CamLock fitting, 3/4" manual air release valve, and station vent.
- 1 Core drill holes into wetwell and provide & install 2" conduits as required with seal-offs between wetwell and pump control panel.
- 1 Provide & install new electrical rack with 3" aluminum posts and stainless steel strut and hardware.
- 1 Provide & install new 60A stainless steel NEMA 4X disconnect switch with 60A fuses.
- 1 Installation of pump control panel & RTU on new electrical rack.
- 1 Installation of Mission RTU equipment on new panel stand.
- 1 Trips by a representative of this company for startup services.

TOTAL PRICE, F.O.B. JOB, FREIGHT INCLUDED **\$102,588.00** PLUS ANY FEDERAL, STATE OR LOCAL TAXES WHICH MAY APPLY. TERMS ARE NET 30 DAYS. PRICES ARE FIRM 30 DAYS

"HYDRA SERVICE INC TERMS & CONDITIONS APPLY" PAYMENT TERMS NET 30 DAYS.

ESTIMATED DELIVERY: **12-14** WEEKS AFTER RECEIPT IN OUR OFFICE OF COMPLETE APPROVED SUBMITTAL DATA AND SIGNED PROPOSAL.

THESE TERMS ARE INDEPENDENT OF, AND ARE NOT CONTINGENT UPON THE TIME OR MANNER IN WHICH PURCHASER MAY RECEIVE PAYMENT FROM OTHERS.

1 DAY OF FACTORY START-UP IS INCLUDED AND REQUIRED FOR WARRANTY. PAYMENT FOR MATERIALS WILL BE REQUIRED BEFORE THE AUTHORIZED START-UP IS CONDUCTED.

ACCEPTED DATE _____

Review Date: 02/27/2026

Dale M. Jahn

NAME OF PURCHASER

REVIEWED BY HYDRA SERVICE PUMP REP.