



# Hydra Service, Inc.

SPECIALIST IN FLUID MOVEMENT



250 Springview Commerce Drive  
 Debarry Florida 32713  
 Phone: 407 330 3456  
 Phone: 800 323 1731  
 Fax: 407 330 3404

**Sales Representative**  
**Contact Information**  
 Cell Phone: 407-790-9751

TO: **City of Edgewater**  
 ATTN: **Ken Tripp**

FROM: **Dale Jahn**  
 EMAIL: [dale@hydraservice.net](mailto:dale@hydraservice.net)  
 DATE: **November 15, 2023**

PH: **802-487-5177**

QUOTE: **230821-7DJ-R2**

EMAIL: [ktripp@cityofedgewater.org](mailto:ktripp@cityofedgewater.org)

REF: **Edgewater LS 14 Conversion**

- 2 Sulzer/ABS model XFP80C-CB1.5-PE28/4 submersible wastewater pump, 3.8hp, 3-230/460v, with 49' of motor cable. Includes hardened impeller & wear plate. Specified duty point: 75 GPM at 30' TDH.
- 2 5 year, 100% warranty for XFP80C-CB1.5-PE28/4.
- 2 4" Sulzer / ABS base elbow (single guide rail design) including slide bracket with hardware and rubber sealing grommet.
- 2 Upper guide rail bracket, 2" single rail, 316 stainless steel.
- 2 15' length of 2" diameter guide rail, 316 stainless steel.
- 2 15' pump lifting chain with shackle, 316 stainless steel.
- 1 Duplex pump control panel to City of Edgewater standards, 3.8hp, 3/230v.
- 4 Liquid level sensing float with 40' of cable.
- 1 Submersible pressure transducer with 40' of cable.
- 1 Mission Communications M152 RTU with 3 year service plan.
- 1 USEMCO factory-built duplex "top vault" system including fabricated aluminum base for 5' diameter wetwell with access hatch, 4" sch 40 316SS piping, cast iron plug valves, cast iron check valves, 4" emergency pump out connection with cast iron isolation valve & CamLock fitting, 2" stainless steel automatic air release valve, station vent, and aluminum panel stand.
- 1 Core drill holes into wetwell and provide & install (3) 2" conduits with seal-offs between wetwell and pump control panel.
- 1 Installation of pump control panel & level sensors on new panel stand.
- 1 Installation of Mission RTU equipment on new panel stand.
- 1 Provide & install electrical service conduit & wiring from existing disconnect / electrical rack to new pump control panel.
- 2 Trips by a representative of this company for startup services.

TOTAL PRICE, F.O.B. JOB, FREIGHT INCLUDED **\$83,795.00** PLUS ANY FEDERAL,  
 STATE OR LOCAL TAXES WHICH MAY APPLY. TERMS ARE NET 30 DAYS. PRICES ARE FIRM 30 DAYS

**"HYDRA SERVICE INC TERMS & CONDITIONS APPLY" PAYMENT TERMS NET 30 DAYS.**

ESTIMATED DELIVERY: **12-14** WEEKS AFTER RECEIPT IN OUR OFFICE OF COMPLETE  
 APPROVED SUBMITTAL DATA AND SIGNED PROPOSAL.

THESE TERMS ARE INDEPENDENT OF, AND ARE NOT CONTINGENT UPON THE TIME OR MANNER  
 IN WHICH PURCHASER MAY RECEIVE PAYMENT FROM OTHERS.

1 DAY OF FACTORY START-UP IS INCLUDED AND REQUIRED FOR WARRANTY. PAYMENT  
 FOR MATERIALS WILL BE REQUIRED BEFORE THE AUTHORIZED START-UP IS CONDUCTED.

ACCEPTED DATE \_\_\_\_\_

Review Date: 11/15/2023

*Dale M. Jahn*

NAME OF PURCHASER

REVIEWED BY HYDRA SERVICE PUMP REP.