



Hydra Service, Inc.

SPECIALIST IN FLUID MOVEMENT



250 Springview Commerce Drive
Debarry Florida 32713
Phone: 407 330 3456
Phone: 800 323 1731
Fax: 407 330 3404

Sales Representative
Contact Information
Cell Phone: 407-790-9751

TO: **City of Edgewater**
ATTN: **Ken Tripp**

FROM: **Dale Jahn**
EMAIL: dale@hydraservice.net
DATE: **November 15, 2023**

PH: **802-487-5177**

QUOTE: **230821-8DJ-R3**

EMAIL: ktripp@cityofedgewater.org

REF: **Edgewater LS 19 Conversion**

- 2 Sulzer/ABS "Piranha" PE28/2 submersible grinder pumps, 3.8hp, 3/230v, each with 32' of motor cable.
- 2 2" Sulzer/ABS base elbow (single guide rail design) including slide bracket with hardware and rubber sealing grommet.
- 2 Upper guide rail bracket, 2" single rail, 316 stainless steel.
- 2 15' length of 2" diameter guide rail, 316 stainless steel.
- 2 15' pump lifting chain with shackle, 316 stainless steel.
- 1 Duplex pump control panel to City of Edgewater specs, 3.8hp, 1/230v. Panel includes Square D VFDs for 1-phase 3-phase conversion.
- 4 Liquid level sensing float with 40' of cable.
- 1 Submersible transducer with 40' of cable.
- 1 Mission Communications M152 RTU with 3 year service plan.
- 1 USEMCO factory-built duplex "top vault" system including fabricated aluminum base for 4' diameter wetwell with access hatch, 3" sch 40 316SS piping, cast iron plug valves, cast iron check valves, 3" emergency pump out connection with cast iron isolation valve & CamLock fitting, 2" stainless steel automatic air release valve, station vent, and aluminum panel stand.
- 1 Core drill holes into wetwell and provide & install (3) 2" conduits with seal-offs between wetwell and pump control panel.
- 1 Installation of pump control panel & level sensors on new panel.
- 1 Installation of Mission RTU equipment on new panel stand.
- 1 Provide & install electrical service conduit & wiring from existing disconnect to new pump control panel.
- 2 Trips by a representative of this company for startup services.

Notes:

- City to provide 1/230v electrical service, 100A suggested. New disconnect by City if required.
- Pricing includes \$10,000.00 contingency for possible changes to pumps and/or accessories.

TOTAL PRICE, F.O.B. JOB, FREIGHT INCLUDED **\$96,752.00** PLUS ANY FEDERAL, STATE OR LOCAL TAXES WHICH MAY APPLY. TERMS ARE NET **30** DAYS. PRICES ARE FIRM 30 DAYS

"HYDRA SERVICE INC TERMS & CONDITIONS APPLY" PAYMENT TERMS NET 30 DAYS.

ESTIMATED DELIVERY: **12-14** WEEKS AFTER RECEIPT IN OUR OFFICE OF COMPLETE APPROVED SUBMITTAL DATA AND SIGNED PROPOSAL.

THESE TERMS ARE INDEPENDENT OF, AND ARE NOT CONTINGENT UPON THE TIME OR MANNER IN WHICH PURCHASER MAY RECEIVE PAYMENT FROM OTHERS.

1 DAY OF FACTORY START-UP IS INCLUDED AND REQUIRED FOR WARRANTY. PAYMENT FOR MATERIALS WILL BE REQUIRED BEFORE THE AUTHORIZED START-UP IS CONDUCTED.

ACCEPTED DATE _____

Review Date: 11/15/2023

Dale M. Jahn

NAME OF PURCHASER

REVIEWED BY HYDRA SERVICE PUMP REP.