ESTIMATE

WB Williamson Bros. Marine
2944 South St, Fort Myers
FL. 33916

George Monroe
Estimator
george@wbwilliamson.com
(448)448-9415

Project:

Veterans Memorial Park Pier (City of Edgewater)

Location:

1851-1899 S Riverside Dr, Edgewater, FL 32141

Proposal Date: 2/20/2026

Proposal Amount:

$405,398.06

Scope of Work: 2,000 sqft dock /pier, complete demo and rebuild

WB Williamson Bros., Inc. is pleased to provide this proposal for the demolition and reconstruction of the Veterans Memorial Park Pier located in Edgewater, Florida.

This proposal reflects the Owner's selection of **Option 2 – Thru-Flow Decking (Gray)** and incorporates the same structural standards utilized in the Menard May Park Observation Pier project, including upgraded piling sizes and cross bracing configuration for enhanced structural performance in a marine environment.

The scope includes, but is not limited to:

- Demolition and removal of existing pier structure
- Furnish and install new **9x30 treated timber pilings**
- Installation of structural framing system
- Installation of **2x8 cross bracing with ½" diameter bolts**
- Installation of **Thru-Flow composite decking – Gray color**
- Marine-grade hardware and fasteners
- Mobilization and demobilization of marine equipment
- Coordination with engineering services

All work shall be performed in accordance with applicable local, state, and federal requirements.

The scope includes, but is not limited to:

- Demolition and removal of existing pier structure
- Furnish and install new **9x30 treated timber pilings**
- Installation of structural framing system
- Installation of **2x8 cross bracing with ½" diameter bolts**
- Installation of **Thru-Flow composite decking – Gray color**
- Marine-grade hardware and fasteners
- Mobilization and demobilization of marine equipment
- Coordination with engineering services

All work shall be performed in accordance with applicable local, state, and federal requirements.

Structural Components

Pilings

9x30 treated timber pilings (substituted from 8x30 due to availability constraints) providing increased structural capacity and durability.

Cross Bracing

2x8 treated timber cross braces secured with ½" diameter bolts for improved rigidity and long-term performance.

Decking

Thru-Flow composite decking system in **Gray**, selected for durability, drainage efficiency, and reduced maintenance in marine conditions.

Contract Pricing

Base Contract – Option 2 (Thru-Flow Decking – Gray)

$395,398.06

Engineering Services

$10,000.00

Total Contract Amount

$405,398.06

Schedule

Upon execution of contract and receipt of Notice to Proceed, WB Williamson Bros., Inc. will coordinate procurement, engineering review, and scheduling in accordance with project requirements.

Material lead times for treated pilings and Thru-Flow decking will be confirmed at time of award.

Acceptance

The undersigned hereby acknowledges receipt of this proposal and agrees to the scope and pricing as outlined above.

Owner / Authorized Representative:

Printed Name:

Title:

Company / Entity:

Signature:

Date: